

TRAFFIC MANAGEMENT PLAN

APPENDIX 2

TRAFFIC MITIGATION MEASURES



NSIC Traffic Management Plan

Ref no:	Topic	Sub-Topic	Mitigation Measure	Phase	Monitoring
CONSTRUCTION (CHAPTER 7, VOLUME 3B) – NOTE ALL OTHER MITIGATION MEASURES ARE ALSO RELEVANT TO CONSTRUCTION MITIGATION					
1.6	General construction	Construction Management	Prior to commencement of construction a full traffic management plan will be produced and implemented.	Pre-construction Phase	Monitoring required during construction
MATERIAL ASSETS – TRAFFIC (CHAPTER 13 OF VOLUMES 3C AND 3D)					
11.1	Development Wide General – Construction Phase	The preparation and implementation of a Construction Traffic Management Plan. The objective of this plan will be to minimise the impact caused by the construction stage of the project	It shall be a requirement of the contractor appointed to construct the project to prepare a detailed Construction Traffic Management Plan prior to the commencement of construction operations. As a minimum, the mitigation measures should include the following: • Development of a detailed construction programme aimed at minimising peaks in traffic volumes on specific roads; • Continuous monitoring of the roads used for construction; • Identification of traffic management measures with respect to road closures; • Measures for continuous liaison with local authorities and other relevant stakeholders; • Identification of traffic management measures at site entrances; and • Measures for accommodating emergency response vehicles along the haul routes.	Prior to the commencement of the construction phase. Continuous updating throughout the construction stage.	Monitoring of roads used during construction stage required.