R937 Latlorcan Pedestrian Crossing

Puffing Crossing Detail with Raised Table Detail
as per Tii CC-SCD-05133 and Tii CC-SCD-05145

Road Markings and General Layout

as per Tii CC-SDC-05127 & Chapter 7 of
the Traffic Signs Manual

400 x 400 mm Tactile Paving (red) to TII Standard Constuction Details: CC-SCD-05135 "Puffin Crossing Tactile Paving and Traffic Signal Details"

Existing footpath and grass verge to be excavated and disposed off site. Existing kerbs to be retained. New Tarmac footpath to be installed either side of crossing as shown to tie into existing levels. Footway to be constructed as per TII Standard Construction Detail CC-SCD-01104 "Kerbs, Footways and Paved Areas, Bitminous Footway", March 2000

Public Lighting Duct to cross Roadway to opposite footpath for future use.

Existing Services covers to be reinstated and raised to finished levels

2no.GY's to connect to existing Road Drainage with 150mm dia. Twinwall Pipe

Ramp Gradient 1:20

Centre of Access Road to Latlorcan

N
W E
S

Project

New Puffin Crossing with Raised Table

Title

Dublin Road - R937
Latlorcan Pedestrian Crossing

/Ŝ ł-yΰ ł₩ . ł₩Ř ł ă ł·ŎK a ₭dzłyŜ ł·ŎK ₤ły
/2 Y ₭ ł·i₩ŧŜ /2yΰ ł·Ŝ a ₭dzłyŜ ł·ŎK ₤ły
hłŦłƎ₦ /2yΰ ł·Ŝ
!y Dŧ Ŝ ł-yy
a dzłyŜ ł·ŎK ₤ły
DdzΰK ₤ y φ мpy yпyyy

a 2y ł·ƎK ł-y a dzyłÕłLJ ł·ŧ 5 ł ă ΰ₦ł Õΰ
a 2y ł·ƎK ł-y /2dzyΰè /2dzyÕłŧ
/2dzyΰè hŦŦłÕŜă
¢K Ŝ Dŧ Ŝy Ť
a 2y ł·ƎK ł-y
¢ Ŝ ŧ Ŝ LJK2yŜ φ мpy yпyyy

Director of Services	Patricia Monahan	
Designed		**Date**
Drawn	EB	**APR 2026**
Traced		**Scales**
Surveyed		
Checked		

É hłŴ ł-yÕŜ {dzdzØŜè ł₩Ŝ ł·yŴł ! ŧ ł₩ƎK ił á ₩ŜáŜł₩ØŜŴł{ ł Õ Ŝy Õ Ŝ
yŵtY ó Ŝł ομημλμπ / / a ! λ a 2y ł·ƎK ł-y / 2dzyΰè / 2dzyÕłŧ