

A copy of this certificate is available on www.fitzsci.ie.

Customer supplied information appear in italics.

Customer	John Quinn Monaghan Co. Co. GWS Glen Road	Lab Report Ref. No.	2224/155/01
		Date of Receipt	28/11/2023
		Sampled On	28/11/2023
		Date Testing Commenced	28/11/2023
		Received or Collected	By Fitz: Pick up Derek
	Monaghan, H18 YT50	Condition on Receipt	Acceptable
Customer PO		Date of Report	02/01/2024
Customer Ref	Monneill Rockcorry	Sample Type	Drinking Water
Ref 2	E265014/N319914		
Ref 3	Audit/StranoodenGWS/2400PRI2021		

CERTIFICATE OF ANALYSIS

Test Parameter	SOP	Analytical Technique	Limit	Result	Units	Acc.
1,2-Dichloroethane (Potable Water)	154	GCMS	3	<0.8	ug/L	INAB
2,3,6-Trichlorobenzoic Acid (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
2,4-D (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
2,4-DB (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Acrylamide (Potable Water)	580	LC-MS-MS	0.1	0.014	ug/L	INAB
Alkalinity (Potable Water)	102	Colorimetry	-	38	mg/L CaCO3	INAB
Ammonium (Potable Water as NH4)	114	Colorimetry	0.5	<0.04	mg/L as NH4	INAB
Antimony (Potable Water)	177	ICPMS	10	<2	ug/L	INAB
Arsenic (Potable Water)	177	ICPMS	10	<2	ug/L	INAB
Atrazine (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Bentazone (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Benzene (Potable Water)	154	GCMS	1	<0.3	ug/L	INAB
Benzo (a) Pyrene	0	By Subcontractor	0.01	<0.003	ug/L	Yes
Benzo (b)-Fluoranthene	0	By Subcontractor	-	<0.005	ug/L	Yes
Benzo (g,h,i)-Perylene	0	By Subcontractor	-	<0.005	ug/L	Yes
Benzo (k)-Fluoranthene	0	By Subcontractor	-	<0.005	ug/L	Yes
Boron (Potable Water) mg/L	177	ICPMS	1.5	<0.02	mg/L	INAB
Boscalid (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Bromate (Potable water)	125	IC	10	<2.4	ug/L	INAB
Bromodichloromethane (Potable Water)	154	GCMS	-	18.4	ug/L	INAB



Signed:

A Harmon

Aoife Harmon - Laboratory Supervisor

Date: 02/01/2024

Acc. : Accredited Parameters by ISO/IEC 17025:2017

Limit as per Monaghan Co Co

For bacterial analysis a result of 0 means none detected in volume examined

All organic results are analysed as received and all results are corrected for dry weight at 104 C

Results shall not be reproduced, except in full, without the approval of Fitz Scientific

Results contained in this report relate only to the samples tested (P) : Presumptive Results

** : The test result for this parameter may be invalid as it has exceeded the recommended holding time (BS EN ISO 5667-3:2018)

* Subcontracted *

Final results will be issued without any estimated uncertainty of measurement being applied. This can be supplied on request.

Fitz Scientific maintain all customer information in the strictest confidence which is legally enforceable.



A copy of this certificate is available on www.fitzsci.ie.

Customer supplied information appear in italics.

Customer	John Quinn Monaghan Co. Co. GWS Glen Road	Lab Report Ref. No.	2224/155/01
		Date of Receipt	28/11/2023
		Sampled On	28/11/2023
		Date Testing Commenced	28/11/2023
		Received or Collected	By Fitz: Pick up Derek
	Monaghan, H18 YT50	Condition on Receipt	Acceptable
Customer PO		Date of Report	02/01/2024
Customer Ref	Monneill Rockcorry	Sample Type	Drinking Water
Ref 2	E265014/N319914		
Ref 3	Audit/StranoodenGWS/2400PRI2021		

CERTIFICATE OF ANALYSIS

Test Parameter	SOP	Analytical Technique	Limit	Result	Units	Acc.
Bromoform (Potable Water)	154	GCMS	-	<2.6	ug/L	INAB
Cadmium (Potable Water)	177	ICPMS	5	<1	ug/L	INAB
Chlorfenvinphos (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Chloride (Potable Water)	100	Colorimetry	250	15.6	mg/L	INAB
Chlorine (Free)	0	By Subcontractor	0.1	0.30	mg/L	
Chlorine (Total)	0	By Subcontractor	0.1	0.50	mg/L	
Chloroform (Potable Water)	154	GCMS	-	51.1	ug/L	INAB
Chlorotoluron (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Chlorpropham (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Chromium (Potable Water)	177	ICPMS	50	<4	ug/L	INAB
Clopyralid (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Clostridia perfringens(Potable)P	161	Anaerobic Incubation	0	0	cfu/100ml	INAB
Copper (Potable Water) mg/L	177	ICPMS	2	0.013	mg/L	INAB
Cyanide (Total)	0	By Subcontractor	50	1.6	ug/L	Yes
Cypermethrin (Acc)	0	By Subcontractor	0.1	<0.012	ug/L	Yes
Diazinon (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Dibromochloromethane (Potable Water)	154	GCMS	-	3.7	ug/L	INAB
Dicamba (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Dichlobenil (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Dichlorprop (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes



Signed:

A Harmon

Aoife Harmon - Laboratory Supervisor

Date: 02/01/2024

Acc. : Accredited Parameters by ISO/IEC 17025:2017

Limit as per Monaghan Co Co

For bacterial analysis a result of 0 means none detected in volume examined

All organic results are analysed as received and all results are corrected for dry weight at 104 C

Results shall not be reproduced, except in full, without the approval of Fitz Scientific

Results contained in this report relate only to the samples tested (P) : Presumptive Results

** : The test result for this parameter may be invalid as it has exceeded the recommended holding time (BS EN ISO 5667-3:2018)

* Subcontracted *

Final results will be issued without any estimated uncertainty of measurement being applied. This can be supplied on request.

Fitz Scientific maintain all customer information in the strictest confidence which is legally enforceable.



A copy of this certificate is available on www.fitzsci.ie.

Customer supplied information appear in italics.

Customer	John Quinn Monaghan Co. Co. GWS Glen Road	Lab Report Ref. No.	2224/155/01
		Date of Receipt	28/11/2023
		Sampled On	28/11/2023
		Date Testing Commenced	28/11/2023
		Received or Collected	By Fitz: Pick up Derek
	Monaghan, H18 YT50	Condition on Receipt	Acceptable
Customer PO		Date of Report	02/01/2024
Customer Ref	Monneill Rockcorry	Sample Type	Drinking Water
Ref 2	E265014/N319914		
Ref 3	Audit/StranoodenGWS/2400PRI2021		

CERTIFICATE OF ANALYSIS

Test Parameter	SOP	Analytical Technique	Limit	Result	Units	Acc.
Dieldrin (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Diflufenican (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Diuron (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Epichlorohydrin (Acc)	0	By Subcontractor	0.1	<0.10	ug/L	Yes
Epoiconazole (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Fluoride (Potable Water)	115	Colorimetry	0.8	<0.08	mg/L	INAB
Fluoroxypyr (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Glyphosate (Potable)	579	LCMS/MS With Derivatisation	0.1	<0.01	ug/L	INAB
Hardness Total (Potable Water)	111	Colorimetry	-	81	mg/L CaCO ₃	INAB
Indeno(1, 2, 3-c,d)pyrene	0	By Subcontractor	-	<0	ug/L	Yes
Isoproturon (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Lead (Potable Water)	177	ICPMS	10	<1	ug/L	INAB
Linuron (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Manganese (Potable)	177	ICPMS	50	<3	ug/L	INAB
MCPA (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
MCP (Mecoprop) (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Mercury (Potable water)	178	ICPMS	1	<0.15	ug/L	INAB
Metaldehyde (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Metazachlor (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Nickel (Potable Water)	177	ICPMS	20	3	ug/L	INAB



Signed:

A Harmon

Aoife Harmon - Laboratory Supervisor

Date: 02/01/2024

Acc. : Accredited Parameters by ISO/IEC 17025:2017

Limit as per Monaghan Co Co

For bacterial analysis a result of 0 means none detected in volume examined

All organic results are analysed as received and all results are corrected for dry weight at 104 C

Results shall not be reproduced, except in full, without the approval of Fitz Scientific

Results contained in this report relate only to the samples tested (P) : Presumptive Results

** : The test result for this parameter may be invalid as it has exceeded the recommended holding time (BS EN ISO 5667-3:2018)

* Subcontracted *

Final results will be issued without any estimated uncertainty of measurement being applied. This can be supplied on request.

Fitz Scientific maintain all customer information in the strictest confidence which is legally enforceable.



A copy of this certificate is available on www.fitzsci.ie.

Customer supplied information appear in italics.

Customer	John Quinn Monaghan Co. Co. GWS Glen Road	Lab Report Ref. No.	2224/155/01
		Date of Receipt	28/11/2023
		Sampled On	28/11/2023
		Date Testing Commenced	28/11/2023
		Received or Collected	By Fitz: Pick up Derek
	Monaghan, H18 YT50	Condition on Receipt	Acceptable
Customer PO		Date of Report	02/01/2024
Customer Ref	Monneill Rockcorry	Sample Type	Drinking Water
Ref 2	E265014/N319914		
Ref 3	Audit/StranoodenGWS/2400PRI2021		

CERTIFICATE OF ANALYSIS

Test Parameter	SOP	Analytical Technique	Limit	Result	Units	Acc.
Nitrate (Potable Water as NO3)	103	Colorimetry	50	7.23	mg/L as NO3	INAB
Nitrite (Potable Water as NO2)	118	Colorimetry	0.5	<0.099	mg/L as NO2	INAB
PAH (sum of 4)	0	By Subcontractor	0.1	<0.020	ug/L	Yes
Pendimethalin (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Pentachlorophenol (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Pesticides Total (Potable)	0	Calculation	0.5	<0.005	ug/L	
pH (Potable Water)	110	Electrometry	6.5 - 9.5	7.03	pH Units	INAB
Picloram (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Propyzamide (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Selenium (Potable Water)	177	ICPMS	20	<3	ug/L	INAB
Simazine (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Sodium (Potable Water)	184	ICPMS	200	14.5	mg/L	INAB
Sulphate (Potable Water)	119	Colorimetry	250	46	mg/L as SO4	INAB
Temperature (On site)	0	By Subcontractor	-	9.6	degree C	
Tetrachloroethene & Trichloroethene (Potable)	154	GCMS	10	<2.32	ug/L	INAB
THM Total (Potable Water)	154	GCMS	100	73.2	ug/L	INAB
TOC (Potable Water)	316	TOC Analyser	-	3.9	mg/L	INAB
Triclopyr (Acc)	0	By Subcontractor	0.1	<0.005	ug/L	Yes
Vinyl chloride (IW Potable Water)	154	GCMS	0.5	<0.07	ug/L	



Signed:

A Harmon

Aoife Harmon - Laboratory Supervisor

Date: 02/01/2024

Acc. : Accredited Parameters by ISO/IEC 17025:2017

Limit as per Monaghan Co Co

For bacterial analysis a result of 0 means none detected in volume examined

All organic results are analysed as received and all results are corrected for dry weight at 104 C

Results shall not be reproduced, except in full, without the approval of Fitz Scientific

Results contained in this report relate only to the samples tested (P) : Presumptive Results

** : The test result for this parameter may be invalid as it has exceeded the recommended holding time (BS EN ISO 5667-3:2018)

* Subcontracted *

Final results will be issued without any estimated uncertainty of measurement being applied. This can be supplied on request.

Fitz Scientific maintain all customer information in the strictest confidence which is legally enforceable.

